BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

NO:EE/YNK-D/E-PMT/01/2015-16 Dated:04-01-2016

MODIFIED APPROVED TENDER SCHEDULE –'B'

Item No: 49

Name of Work: -Improvements to roads and drains in Bharath Nagara and Chandrappa Layout in Ward No-03 Yelahanka Satellite Town Sub Division Change Of Work Providing and Laying Pipeline in Attur Ward No-03

Sl.No	Description of work	Unit	Approved Qty	Approved Rate	Rate in words
1	KSRB 2-2.2 : Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m , in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. specification, specification. No. KBS 2.1(b) / 2.3.5, No. 5/ Item No. 2.4/ PWD SR 2015-16	Cum	1414.20	281.86	RupeesTwo hundred eighty one and eighty six paise only
2	Providing and instalation at site of works P.V.C.Pipes including cost of pipes and specials and incluidng lowring into trenches, laying true to line, level and perfect linking at joints, leak proof including jointing encasing the pipe alround to a depth Not less than 15cm with grave or selected earth avalabile from the execavation Etc., Page No.3 item No.4.2 PRE SR2008-09.				
	63mm dia 6KSC	Rmtr	2120.00	114.89	Rupees one hundred fourteen and eighty nine paise only
	75mm dia 6KSC	Rmtr	480.00	161.05	Rupees One hundred sixty one and five paise only
3	Supplying of ISI marked galvanized mild steel tube (continously welded electric resistance welded (ERW) high frequency, induction welded (HFIW) Hot finished welded type of nominal bore given below screwed at both ends as per IS 554/1986 with latest amendments, pipes threaftes at one end and the other end protected asper specification in random lengths of 4 to 7 mtrs Confirming to IS 1239 part I/1990 with amendament 1-5 and with all its latest amendements if any. The pipes supplied should be with BIS mark No 3/08-09 2406/15.10.2008. 50 mm dia including Collar Heavy Class 2015-16, P-90, i.no13.15	Rmtr	12.00	442.11	Rupees four hundred forty two and Eleven paise only

4	ksrb13-9.1;Providing and fixing to wall.ceiling and high density polythylene pipes 6.00kgf/sq.cm working pressure 32mm outside diameter raising mains &exposed distrubution pipes with special flange,compression type fittings,wall clipps,making good the wall,ceiling and floor,including cost of all materials,labour charges,HOM of equipments and testing complete as per specifications.Specfication no.KBS 13.2.15.2/13.9 63 mm dia 2015-16, P-94, i.no13.73.2	Rmtr	50.00	365.26	Rupees three hundred sixty five and twenty six paise only.
5	KSRB 2-4 : Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50mm, and lift upto 1.5m, including cost of all labour complete as per specifications, No. 6/ Item No. 2.11/ PWD SR 2015-16	Cum	1414.20	76.00	Rupees seventy six only
6	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper conductor confirming to table 3 class 5 of IS:8130-1984 and virgin grade PVC insulation and sheathed suitable for working voltage upto 1100 Volts. P. No. 46/ I No. 30-B 4.0 Sqm mm of 36 strands 0.3mm dia Group - A KPWD Electrical SR 2007-08 3/2008-09 4538/19.01.2009 (1x3x6.00 Sqmm PVC cable)	Rmtr	400.00	187.93	Rupees one hundred eighty seven and ninety three paise only.
7	KSRB 13.6.3-6 : Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 50mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No. KBS 13.2.6/13.3 (P.89/I.13.37 PWD SR - 2015-16)	Each	31.00	2111.30	Rupees Two thousand one hundred eleven and thirty paise only

Signature of the contractor.

Executive Engineer,
Yelahanka Division,
BBMP, Bangalore.